



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 25, 1995

F G Holl Company L L C
6427 E Kellogg P O Box 780167
Wichita KS 67278-0167

Cudney A 1
API 15-047-20,480
1250 FNL 2640 FEL
Sec. 04-26S-16W
Edwards County

Dear Art Merrick,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760

10-30-79

RECEIVED
KANSAS CORPORATION COMMISSION

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

JAN 23 1995

CONSERVATION DIVISION
WICHITA, KS

WELL LOG - - - - - CUDNEY "A" #1-4
Located: 1250' S CNL, Section 4-26S-16W, Edwards County,
Kansas

OWNER: F. G. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 2, 1979
COMPLETED: February 9, 1979

TOTAL DEPTH: 4505'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 406 Shale and Sand	Ran 11 joints new 24#, 8 5/8" casing, 390.56' set at 403' K.B. with 350 sacks 60/40 Pozmix with 3% cc. Plug down at 4:45 PM, 2-2-79, by Howco.
406 - 935 Shale, Sand and Red Bed	
935 - 1082 Red Beds	
1082 - 1099 Anhydrite	
1099 - 2228 Shale and Lime Strs.	
2228 - 4370 Shale and Lime	
4370 - 4437 Lime, Shale and Chert	
4437 - 4483 Lime and Shale	
4483 - 4505 Chert and Lime	Ran 144 joints new 40.5#, 4 1/2" casing, 4490.76' set at 4500' K.B. with 50 sacks Howco Light and 150 sacks 50/50 Pozmix with 18% salt and 5# Gilsonite and 1/8# Flocele and 1/8# Tuffiber and 3/4% CFR-2 per sack. 250 gal. mud flush and 20 bbl. salt flush ahead of cement. Plug down at 8:15 AM, 2-9-79, by Howco.