

KANSAS STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION

Well Location SE SW NE Sec. 15 Twp. 26S Rge. (E) 9 (W)

Field Name (if any) Lorado County Reno

Lease (Farm Name) Mary Whipple Well No. 4

Was well log filed with application? Yes If not, explain circumstances and give available data (Use an additional sheet if necessary)

Will the plugging of the well be done in accordance with the Rules and Regulations of the Kansas State Corporation Commission? Yes If not, explain fully exceptions desired (Use additional sheet, if necessary)

Date plugging is desired to begin Immediately

Name of the person on the lease in charge of well for owner

B. L. Gilmer Address Box 744, Great Bend, Kansas

Name of well owner or acting agent Shell Oil Co., Inc.

Address c/o W. M. Gholson, Box 744, Great Bend, Kansas

To whom should invoice covering assessment for plugging well be sent?

Shell Oil Co., Inc. Address c/o W. M. Gholson, Box 744, Great Bend, Kansas

[Signature]
Operator or Acting Agent
Date December 11, 1945
KANSAS STATE CORPORATION COMMISSION
DEC 14 1945
12-14-45

FILE
BOOK PAGE 26-27
15 26 9W
27



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA 2, KANSAS

December 19, 1945

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Well No. ⁴ Mary Whipple
Lease SE SW NE 15-26-9W
Description None
County 36-27
File:

Shell Oil Co., Inc.
Box 744
Great Bend, Kansas

Gentlemen:

This letter is your permit to plug the
above subject well, in accordance with the
Rules and Regulations of the State Corpora-
tion Commission.

Very truly yours,

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

HA

BY:

J. P. Roberts
J. P. ROBERTS

Ruel Durkee
McPherson, Kansas

NOTICE:


Snell, Mary Whipple #4
SE SW NE 15-26S-9W
Lorado Pool
Reno County, Kansas

CASING RECORD

10 $\frac{3}{4}$ " cem 300 with 300 sax
7" cem 4141 with 300 sax

0 - 110 sand
300 red rock
415 red rock & shale Drlg 9" hole
1030 shale & snells
1154 salt & shale
1303 broken lime & shale
1481 lime & shale
1533 lime & sand
1596 lime & shale
1649 broken lime
1735 shale & red rock
2170 shale & lime
2185 lime
2206 shale
2275 shale & lime snells
2888 shale & lime
2925 lime
3241 lime & shale
3314 lime & shale breaks
3345 lime & shale
TOP STANTON LIME 3345
3630 lime
3800 lime & shale
3820 shale
3869 lime & shale
3877 shale
TOP MISS. CHAT 3877
3886 chat
3925 chert
3965 lime
4134 shale
4139 lime
4141 shale
TOP TRENTON LIME 4141
4146 dolomite T.D. 6 $\frac{1}{2}$ " hole.

15 26 9W
36 27



DEC 14 1945