

KANSAS STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION

Well Location NE NW SE Sec. 15 Twp. 26S Rge. (E) 9 (W)

Field Name (if any) Ierado County Reno

Lease (Farm Name) E. L. Adkins Well No. 1

Was well log filed with application? Yes If not, explain circumstances and give available data (Use an additional sheet if necessary)

Will the plugging of the well be done in accordance with the Rules and Regulations of the Kansas State Corporation Commission? Yes If not, explain fully exceptions desired (Use additional sheet, if necessary)

Date plugging is desired to begin Immediately

Name of the person on the lease in charge of well for owner

B. L. Gilmer Address Box 744, Great Bend, Kansas

Name of well owner or acting agent Shell Oil Co., Inc.

Address c/o W. M. Gholson, Box 744, Great Bend, Kansas

To whom should invoice covering assessment for plugging well be sent?

Shell Oil Co., Inc. Address c/o W.M.Gholson, Box 744, Great Bend, Kansas

PLUGGING
FILE 15 26 94
BOOK PAGE 36 OF 22

[Signature]
Operator or Acting Agent
Date December 11, 1945
DEC 14 1945
12-14-45



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA 2, KANSAS

IN REPLY PLEASE
REFER TO THIS
SUBJECT

December 19, 1945

Well No.
Lease
Description ¹ E. L. Adkins
County NE NW SE 15-26-9W
File: Reno
36-22

Shell Oil Co., Inc.
Box 744
Great Bend, Kansas

Gentlemen:

This letter is your permit to plug the
above subject well, in accordance with the
Rules and Regulations of the State Corpora-
tion Commission.

Very truly yours,

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

HA

BY: J. P. Roberts
J. P. ROBERTS

NOTICE:

Russl Durkee
McPherson, Kansas

Shell, E. L. Adkins #1
NE NW SE 15-26S-9W
Ierado Pool
Reno County, Kansas

CASING RECORD

10³/₄" cem 282 with 300 sax
7" cem 4143 with 300 sax

0 - 150 clay & sand
282 red rock
515 shale & lime snells Drlg 9" hole
715 shale & snells
900 shale & snells
1255 shale & lime
1292 shale & snells
1371 lime & shale
1418 shale & gypsum
1492 lime & shale
1544 lime
1570 shale & lime
1607 lime
1756 lime & shale
1778 lime
2410 lime & shale
2430 lime
2479 broken lime
2576 lime
2722 lime & shale
2770 shale
2782 lime
2876 lime & shale
2901 lime
3045 shale & snells
3179 lime
3355 lime & shale
TOP STANTON LIME 3355
3621 lime
3790 lime & shale
3871 shale, hard
3885 shale
TOP MISS CHAP 3885
3929 chat
3941 lime
3960 lime & shale
4113 shale TOP KINDERHOOK SHALE 3960
4139 shale & lime
4142 lime
4143 shale
4143¹/₂ chert
4144 chert & dolomite
TOP TRENTON LIME 4143
4146 dolomite TD

FILE

15 26 9W

BOOK

36 22

FEB - 6 1946

DEC 14 1945