

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission,
800 Bitting Building,
Wichita, Kansas

Reno County. Sec. 15 Twp. 26 Rge. (E) 9 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 330' from N. 330' from E.

Lease ~~Of~~ The Ohio Oil Company

Lease Name W. C. Lawson Well No. 2

Office Address McPherson, Kansas.

Character of Well (Completed as Oil, Gas or Dry Hole) Oil

Date, well completed January 27, 1937

Application for plugging filed 1937

Application for plugging approved September 9, 1938

Plugging Commenced October 13, 1938

Plugging Completed October 15, 1938

Reason for abandonment of well or producing formation Encroachment of salt water and inability to make 1/6% allowable

If a producing well is abandoned, date of last production August 31, 1938

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Guy Wiershing

Producing formation Viola Depth to top 4148 Bottom 4154 Total Depth of Well 4154 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola	Oil & Water	4148	4154	15 $\frac{1}{2}$ 7	342' 4147	None 1781

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cemented at bottom of hole from 4154 to 4135, 17' above viola. Filled with heavy mud between plugs from 4135 to top of hole. Plug and 15' cement at top of chat 3904 to 3889.


Plug, rock and 15' cement above surface pipe at 342'.

Plug, Rock and 10' cement at base of cellar. The cement was dumped with bailer except at base of cellar.

The mud and rocks were broken in small pieces and dropped in hole.

PLUGGING
FILE SEC 15 T 26 R 2W
BOOK PAGE 32 LINE 331

11-5-38



(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to The Ohio Oil Company
Address McPherson, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Bruce Aug (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce Aug

Box 710 McPherson Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4 day of NOV., 1938.

My commission expires Feb. 11, 1941.

A. J. McClintick
Notary Public.