

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR R & B Oil & Gas, Inc.

ADDRESS 111 N. Blane, Attica, KS 67009

PHONE: (316) 254-7251 OPERATORS LICENSE NO. 31191

Character of Well

(Oil) Gas, O&A, SWD, nput, Water Supply Well

The plugging proposal was approved on APR 24 2001 4-24-01 (date)

by David P. Williams CONSERVATION DIVISION (KCC District Agent's Name).

is ACO-1 filed? Yes If not, is well log attached? not available to us

Producing Formation Viola Depth to Top 4144 Bottom 4202 T.D. 4265

Show depth and thickness of all water, oil and gas formations.

OIL GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	290	none
Viola	Oil	4144	4202	5 1/2	4250	2229

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each section.

Ran sand, loaded hole, sanded 3620, baled 5 sacks cement. Shot pipe at 2829, 2229, pulled 22 fts. to 1350. Pump 35 sacks cement at 1350, pulled 13 fts. to 800, pumped 55 sacks and pulled 11 fts. to 340. Circulated to top with 5 sacks.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925


Address 415 East Main, Sterling, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R+B Oil + Gas, Inc.

STATE OF Kansas COUNTY OF Harper, ss

Randy Newberry (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Randy Newberry
 (Address) PO Box 195, Attica, KS 67009



SUBSCRIBED AND SWORN TO before me this 23rd day of April 192001

Rebecca S. Newberry
 Notary Public

My Commission Expires: 7-21-2001

USE ONLY ONE SIDE OF EACH FORM

OR