

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 18 Twp. 26 Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines SE NW NW

Lease Owner Sohio Petroleum Company

Lease Name T. M. Wells Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 8-2 1955

Application for plugging filed 8-4 1955

Application for plugging approved 8-4 1955

Plugging commenced 8-2 1955

Plugging completed 8-2 1955

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Durkee

Producing formation Depth to top Bottom Total Depth of Well 4418 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing				8-5/8	360'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4418' to 355' - Heavy Mud
355' to 30' - Bridge and 20 sacks cement & mud
30' to Cellar - Bridge & 5 sacks cement

*Reed
8-5-55*

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Birmingham - Bartlett Drilling Company
Address Wichita, Kansas


STATE OF KANSAS, COUNTY OF RUSSELL, ss.
J. H. BOND (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. H. Bond*
Box 613, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of August, 1955

Dwight B. Brown
Notary Public.

My commission expires January 24, 1959



T. M. WELLS NO. 1 WELL

LOCATION: SE/4 NW/4 NW/4
Section 18-26S-9W
Reno County, Kansas

SPUDED: 7-17-55
COMPLETED: 8-2-55

OWNER: Sohio Petroleum Company
Box 673
Russell, Kansas

CONTRACTOR: Birmingham-Bartlett Drilling Co.
300 Kaufman Building
Wichita 2, Kansas

SURFACE CASING: 8-5/8 inch 24# casing cemented at
355 feet with 250 sacks cement and
5 c. c.

OIL STRING: None set. Dry and abandoned.

LOG

(Figures indicate bottom of formation)

0	35	Sand
	100	Clay and sand
	355	Red bed
	615	Red bed, shale, and shells
	625	Anhydrite
	1370	Shale and shells
	3455	Lime and shale
	3987	Lime
	4191	Shale
	4307	Lime
	4335	Shale and lime
	4370	Shale and chert
	4418	Lime
	4418	Rotary Total Depth

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the T. M. Wells No. 1 well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me
this 4th day of August, 1955.

Beverly Larson
Beverly Larson, Notary Public

My commission expires October 2, 1958.

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1955
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
WEL SEC 18 T 26R 9W
BOOK PAGE 140 LINE 6