


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County. Sec. 5 Twp. 26S Rge. 8W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Anschutz Drilling Co., Inc.
Lease Name Gardner Well No. 1
Office Address 709 Union Natl. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 14 1956
Application for plugging filed September 15 1956
Application for plugging approved September 15 1956
Plugging commenced September 15 1956
Plugging completed September 15 1956
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4372 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	205'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug @ 180' with 15 sacks cement.
Second plug @ 20' with wire line and 5 sacks cement.

9-22-56
STATE CORPORATION COMMISSION
WICHITA, KANSAS
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Anschutz Drilling Co., Inc.
Address 709 Union Natl. Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Shirley Salley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Shirley Salley
709 Union Natl. Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1956
Kenneth R. Swenson
Kenneth R. Swenson Notary Public.

My commission expires April 27, 1959

PLUGGING
FILE SEC 5 T 26 R 8W
BOOK PAGE 100 LINE 3

DRILLERS' LOG

ANSCHUTZ DRILLING CO., INC.
 #1 GARDNER
 NE NE SW Sec. 5-26S-8W
 Reno County, Kansas

15-55-00014-0000

<u>FROM</u>	<u>TO</u>	
0	215	Red bed
215	400	Red rock
400	760	Red bed and shale
760	1060	Salt
1060	1150	Shale
1150	1485	Lime and shale
1485	1800	Lime
1800	2140	Lime and shale
2140	2330	Shale with lime streaks
2330	3105	Lime and shale
3105	3335	Shale and lime
3335	3515	Lime
3515	3555	Lime with shale streaks
3555	3825	Lime
3825	3886	Lime and shale
3886	3895	Mississippi
3895	3957	Chert
3957	4129	Lime and shale
4129	4214	Shale and lime
4214	4263	Viola
4263	4300	Simpson
4300	4337	Shale and lime
4337	4372	Arbuckle
	4372	Total Depth

COMMENCED: 8/29/56

COMPLETED: 9/14/56

CASING RECORD:


Set 205' of 8-5/8" surface casing with 150 sacks cement, 2% gel., 200# calcium chloride

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the formations encountered on the #1 Gardner, NE NE SW of Section 5-26S-8W, Reno County, Kansas, as reflected by the daily drilling reports.

ANSCHUTZ DRILLING CO., INC.

By: Shirley Salley
 Shirley Salley



Subscribed and sworn to before me this 20th day of September, 1956.

My Commission Expires: April 27, 1959

Kenneth R. Swenson
 Kenneth R. Swenson, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 22 1956
 CONSERVATION DIVISION

PLUGGING
 FILE SEC 5 T26 R 8W
 BOOK PAGE 100 LINE 3