


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Reno _____ County. Sec. 10 Twp. 26S Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines APP. SE/4 SE/4 NE/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Reece 'B' Unit Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 28 1958
Application for plugging filed September 28 1958
Application for plugging approved September 28 1958
Plugging commenced September 28 1958
Plugging completed September 28 1958
Reason for abandonment of well or producing formation dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3936 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	198'	none
				4-1/2"	3936'	2696'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 195' and set
plug and 195' w/20 sx. cement,
Mud to 40' and set plug at 40'
w/10 sx. cement, mud to surface

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1958

10-29-58
DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messman-Rinehart Oil Company
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October 1958

My commission expires December 1, 1960
Barbara J. Scott
Barbara J. Scott, Notary Public.

PLUGGING
FILE SEC 10 T 26 R 9W
BOOK PAGE 136 LINE 22

15-155-02071-0000

NO. 1 REECE "B" UNIT

Well Record

Location:	App. SE SE NE, Sec. 10-26S-9W Reno County, Kansas	Commenced:	July 19, 1958
Operator:	Messman-Rinehart Oil Company 518 Petroleum Building Wichita, Kansas	Completed:	July 31, 1958 (rotary)
Contractor:	Messman-Rinehart Oil Company 518 Petroleum Building Wichita, Kansas	Elevation:	1680' K/B
		Production:	Gas

Casing Record: 8-5/8" @ 198' w/175 sx. cem., 3 c.c., 2 gal.
4-1/2" @ 3936' w/175 sx. cem., 3 gal.

*** LOG ***

Clay & Sand	73
Red Bed	285
Red Bed & Shale	1070
Shale	1235
Anhydrite	1270
Shale & Shells	1335
Lime & Shale	1730
Lime	1945
Lime & Shale	3338
Lime	3673
Lime & Shale	3875
"Miss" Chert	3895
Chert	3930
Lime	3936

Sample Tops:

3330 (-1650)	Brown Lime
3360 (-1680)	Lansing
3876 (-2196)	Mississippi "Chat"
3930 (-2250)	Mississippi Lime

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By:

J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me
this 7th day of August, 1958

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1960

RECEIVED

INCORPORATION COMMISSION

OCT 29 1958

CONSERVATION DIVISION

PLUGGING

FILE SEC. 10 T. 26R 9W

BOOK PAGE 136 LINE 22

COMPLETION DATANO. 1 REECE "B" UNIT

App. SE/4 SE/4 NE/4
 Section 10-26S-9W
 Reno County, Kansas

- 8-6-58 - Moved in cable tools
 8-7-58 - Ran Lane-Well's Log - 3880' Miss. Chat (-2200)
 - Perforated 3876-83' w/4^s per ft.
 8-8-58 - Treated with 500 gal. mud acid, swabbed well in to flowing,
 Made 2,000-3,000 Mcfg and 13 bbls. water per hr.
 8-9-58 - Squeezed with 150 sx. cement, drilled out cement, and
 re-perforated 3876-81' w/3^s per ft. (cone) and vibra-frac (15)
 8-13-58 - Swabbed back, made 200,000 cfg (esti.) and 1 BWPH (decreasing)
 Treated w/300 gal. acid, Made 2,000-3,000 Mcfg and 13 BWPH
 8-17-58 - Killed well
 8-28-58 - Ran radioactivity tracer survey - determined water coming
 from 3910' (-2230), Squeezed with 250 sx. cement, drilled
 out cement and started getting water, DDC to 3910' and
 found collapsed joint at 3885', Perforated at 3910' w/4 cone
 shots, Squeezed again w/200 sx. cement and drilled out cement
 to 3883' (2' below perf.), Treated w/300 gal. mud acid, had
 1,000 Mcf (esti.) and leaked 8-10 BWPH, Squeezed with 60 sx.
 latex cement, drilled out cement and swabbed well in to
 flowing, flowed back 11 bbls. fluid over load
 9-13-58 - Making 12 BWPH and 1/2-3/4 million cubic feet gas (esti.)
 Preparing to abandon

MESSMAN-RINEHART OIL COMPANY

By: Roger L. Messman
 Roger L. Messman

RLMbs

RECEIVED
 STATE CORPORATION

OCT 29 1958

DIVISION