

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER #15-047-20,516-0000

LEASE NAME Cudney B

WELL NUMBER #2-4

 Ft. from S Section Line

 Ft. from E Section Line

SE SE NE

SEC. 4 TWP. 26 SRGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 7-26-88

Plugging Completed 7-28-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sterling Drilling Company

ADDRESS Box 129
Sterling, Kansas 67579

PHONE # (616) 278-2131 OPERATORS LICENSE NO. 5142

Character of Well Oil

(Oil, Gas, D&A; SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	416'	none
				4-1/2"	4521'	2353'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4390' and 4 sacks cement. Shot pipe @2353', pulled a total of 54 joints of 5-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 120 cement, 60/40 pos., 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) Box 347 Chase, Kansas 67524

RECEIVED
STATE CORPORATION COMMISSION
AUG - 9 1988
8-9-88

SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 88

Irene Hoover
Notary Public

INSPECTION DIVISION
Wichita, Kansas

Commission Expires:

