

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RETURN
K.A.R.-82-3-117

API NUMBER 15-047-20537-0000

LEASE NAME Parker

WELL NUMBER 4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 4 TWP. 26S RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 11-18-96

Plugging Completed 11-21-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Great Eastern Energy

ADDRESS 5990 Greenwood Plaza Blvd #116 Englewood, CO 80111

PHONE# (303) 773-6016 OPERATORS LICENSE NO. 9449

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4429'

Show depth and thickness of all water, oil and gas formations.

12-3-96

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	459'	none
				5 1/2	4427'	2222'

REC-3
KANSAS
RECORDS
DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each section. Sanded bottom to 4010' & ran 5 sks cement. Shot at 2522', 2416' & 2222'. Pipe came free at 2222'. Pulled to 2180', pumped 10 sks gel spacer followed by 40 sks cement. Pulled to 1070' & mixed 10 sks gel spacer followed by 50 sks cement. Pulled csg to 500', spotted 50 sks cement. Pulled rest of csg & topped w/30 sks. Plugging complete. 60/40 6%.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Eastern Energy

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 96

James Schubert
Notary Public

My Commission Expires:

