



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)

500 Insurance Bldg.
WICHITA, KANSAS

RECEIVED
CORPORATION COMMISSION
21 DEC 17 1968
CONSERVATION DIVISION
Wichita, Kansas

12-17-68

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 6, 1968

15-155-00082-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Pafford Well No. 1

Location: NW NW NE Sec. 12 Twp. 26 Rge. 9 (E)(W) X

County: Reno Total Depth 3981' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

(Operator had filled hole with sand to 3790') Dump 5 sacks cement on
sand at 3790'. Fill hole with mud to 230'. Set rock bridge from 230'
to 220' and cement hole with 25 sacks cement. Fill hole with mud to 40'.
Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent