

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN P. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

November 27, 1964

11-30-64

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

\* Mr. Don Lore of White & Ellis Drlg., Inc has this  
date requested permission to plug the following described well:

Mr. Lore guarantees payment of the plugging fee.

Operator's full Name: William H. Pine

Complete Address: Mc Cullough Bldg., Okmulgee, Oklahoma

Lease Name: Mc Cullough Well No. 1

Location: C SW SW Sec. 36 Twp. 26 Rge. 8  (W)  (X)

County Reno Total Depth 3705' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Lore was instructed to plug the well as follows:

Fill hole with mud to 190'. Push plug and 1/2 sack hulls to 190' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Plugging Fee to be billed to: Very truly yours,

\* White & Ellis Drilling, Inc.  
Box 448  
F1 Dorado, Kansas

[Signature]  
Conservation Division Agent