

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

December 26, 1969

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1969 12-30-69

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cecil Prier of Henry Wofford Drilling Co. has this date requested permission to plug the following described well:

Mr. Prier guarantees payment of the plugging fee.

Operator's full Name: Woco, Inc.

Complete Address: 1016 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name: N. E. Miller Well No. 1

Location: C E/2 NE Sec. 6 Twp. 24 Rge. 4 ~~(E)~~ (W) X

County: Reno Total Depth 3407' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Prier was instructed to plug the well as follows:

Fill hole with mud to 280'. Push plug and 1/2 sack hulls to 280' and
cement hole with 35 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 15
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent