



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

November 22, 1965

15-155-19095-6000

RECEIVED  
CORPORATION COMMISSION  
NOV 29 1965  
CONSERVATION DIVISION  
Wichita, Kansas

11-29-65

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Neunemaker "F" Well No. 1

Location: C W/2 NW Sec. 12 Twp. 26 Rge. 9 (E)(W) X

County Reno Total Depth 3970' Oil Well     

Gas Well X Input Well      SWD Well      D & A      Lost Hole     

Mr. Lamb was instructed to plug the well as follows:

Push 4 1/2" plug to 3200'. Fill hole with sand to 3190' and cement with 3 sacks. Fill hole with mud to 230'. Set rock bridge from 230' to 220' and cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent