

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-047-10017-00-01

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed May 2, 1967.

Dear Sir:

Mr. George Klein of Messman-Rinehart Oil Co. has this
date requested permission to plug the following described well:

Mr. Klein guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: C.R. Wood Well No. # 1

Location: C NE NE Sec. 22 Twp. 26 Rge. 16 (E)(W) W

County Edwards Total Depth 3179 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Klein was instructed to plug the well as follows:

1065' of 8 5/8" surface pipe, cement circulated. Fill hole with
drilling mud to 500', 1st cementing plug, bridge with 1/2 sack of hulls,
and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd
cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks
to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent