

RECEIVED
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3
Rev. 1-8-82

OCT 01 1982

STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas
CONSERVATION DIVISION AGENT REPORT

API Number 15-047 70294-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Benson Mineral Group Inc. # 5817

Complete Address 1726 Champ St. Suite 600 Denver Colo 80202

Lease Name Schultz 'B' Well No. 1

Location C-NW-NE Sec. 21 Twp. 26 Rge. 16 (East)(West)

County Edwards Total Depth 4605'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor H H Casing Pulling

Address 408 circle drive Box 563 Benton Kans 67020 License No. 6053

Operation Completed: Hour: 5:00 PM Day: 27 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

5 1/2" @ 4572' perf. 4115' to 24'. 1st plug sandbed bottom back to 4065' & dumped 5 sbk cement on sand. 2nd plug pumped through sand on 8 5/8" w/ 3 sbk bulls, 1 gell & 50 sbk cement, 1 bull & 15 sbk gell & release rubber plugs followed with 100 sbk cement. The cement used was 50/50 pos w/ 2% gell & 3% cc. The plugging was accomplished by Allied Cementing. Mr. Bud Metz was on location when top plug was pumped. Max pressure was 500# shut in at 200#

Amount of Surface Casing: 8 5/8" @ 450' cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 10-14-82

UNCL. NO. 1319-6A