

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-047 - 20864-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Benson Mineral Group Inc. #5817

Complete Address 1726 Champa St. Suite 600, Denver Colo. 80202

Lease Name Shulky 2' Well No. 1-21

Location C-NE-SE-NW Sec. 21 Twp. 26 Rge. 16 (East)(West)

County Edwards Total Depth 4638'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H. & H. Casing Pulling

Address 408 Circle Drive Box 563 Burton Kans 67020 License No. 6053

Operation Completed: Hour: 1:30 PM Day: 27 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All  Part  None  *Top plug*

The above well was plugged as follows:

4 1/2" @ 4633' w/260 sb/cemt. perf. 45'30" to 46'. 1st plug  
sanded bottom back to 4560' & dumped 4 sb/cemt on sand. 2nd  
plug pumped through head sup/50/50 por mix 23 gells 3% C.C.  
Pumped 3 hulls 10 gells 50 cmt. & 1 hull 15 gells released rubber  
plug & followed it w/100 sb/cemt. max. pressure 200# shut in  
at 100# pressure. They recovered 1830' of 4 1/2" pipe. The plugging  
was accomplished by allied cementing. Mr. Bud Metz  
was on location when plugging top.

Amount of Surface Casing: 8 1/8" @ 479' w/400 sb/cemt.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luttig  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
OCT 01 1982  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICE  
DATE 10-14-82  
INV. NO. 1321-W