

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047 - 26869-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Benson Mineral Group Inc. # 5817

Complete Address 1726 Champa St. Suite 600, Denver Colo. 80202

Lease Name Shultz "M" Well No. 1-21

Location 2140' FVL + 2310' FSL Sec. 21 Twp. 26 Rge. 16 (East) (West)

County Edwards Total Depth 4675'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor H+H casing pulling

Address 408 Wick Drive Box 563 Burton Kans 67020 License No. 6053

Operation Completed: Hour: 2:50 P.M. Day: 27 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part Top plug None

The above well was plugged as follows:

4 1/2" @ 4661' w/ 150 lbs cent. perf 4530' to 50' 1st plug sandbed
bottom back to 4480' w/ 4 lbs on top of sand. 2nd plug pumped
through 8 5/8" head 3 lbs bulls 10 lbs gells 50 lbs cent. 1 lb bulls
15 lbs gells release rubber plugs followed it w/ 100 lbs cent.
Cement used was 50/50 poz. w/ 2 1/2 gells 3% CC. They recovered
2787' of 4 1/2" pipe. The plugging was accomplished by
Allied Cementing. Mr. Bud Metz saw the top plug
pumped. The max. pressure was 200# then went on vacuum.

Amount of Surface Casing: 8 5/8" @ 469' w/ 400 lbs

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Raul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE RECEIVED
OCT 01 1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 10-14-82
INV. NO. 1322-W

Signed: _____
Conservation Division Agent