

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1967

CONSERVATION DIVISION
Wichita, Kansas

5-11-1967

15-047-100(7-00-61

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed May 2, 1967.

Operator's Full Name Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name C. R. Wood Well No. # 1

Location C NE NE Sec. 22 Twp. 26 Rge. 16 (E) (W) (W)

County Edwards Total Depth 3179'

Abandoned Oil Well Gas Well Input Well SWD Well D & A ^{OWWO} X

Other well as hereafter indicated: This hole was a wash down.

Plugging Contractor: Murfin Drilling Company

Address: 617 Union Center Bldg., Wichita, Kansas 67202 license No.

Operation Completed: Hour 4:15PM Day 8th Month May Year 1967

The Above well was plugged as follows:

1065' of 8 5/8" surface pipe, cement circulated. Fluid level in the hole
was at 300'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to
500', and cemented with 25 sacks, through the drill pipe. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.
This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlie Elving
Well Plugging Supervisor

DATE 5/11/67

INV. NO. 5200-W