

15-047-1007-0000

Form CP-3
Rev. 6-26-62

10

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1966
8-17-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Wichita Iron & Metals Corporation, Inc.

Complete Address: Box 13021, Wichita, Kansas

Lease Name Wood Well No. # 1

Location C NE NE Sec. 22 Twp. 26 Rge. 16 (E) (W) W

County Edwards Total Depth 4506'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:30AM Day 11th Month August Year 1966

The Above well was plugged as follows:

102' of 12 1/2" surface pipe, cement circulated. 1065' of 8 5/8" surface pipe, cement circulated. 4504' of 4 1/2" long string, cemented with 225 sacks. Top perforation 4400'. Bottom of the hole was sanded to 4350', and cemented with 3 sacks, through the dump bailer. 3200' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 400', rock bridge from 400' to 390'. 2 sacks of cement was mixed in a barrel, and put on plug at 390', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 23 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/17/66

INV. NO. 3790-W