

RECEIVED
STATE CORPORATION COMMISSION
OCT 01 1982
CONSERVATION DIVISION
Wichita, Kansas

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-047 - 20713-00-01

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Benson Mineral Group Inc. #5817

Complete Address 1726 Champa St. Suite 800 Denver Colo 80202

Lease Name Schultz "H" Well No. 1-11

Location NE SE SW-NE ? Sec. 11 Twp. 26 Rge. 16 (East) (West)

County Edwards Total Depth 4500'

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated ☐

Plugging Contractor H. A. H. Casing Pulling

Address 408 Circle Drive Box 563 Burton Kans 67020 License No. 6053

Operation Completed: Hour: 9:25 A.M. Day: 27 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All ☐ Part Top plug None ☐

The above well was plugged as follows:

4 1/2" @ 4500' w/ 250 lbs cement. 1st plug sanded back bottom to 4320' dumped 4 lbs cement on top of sand to cover perf. which were from 4370' to 4412'. 2nd plug pumped through head on 8 5/8" with 3 lbs hulls 10 lbs gell & 50 lbs cement 1 lbs hulls & 15 lbs gell & released rubber plug & followed it with 100 lbs cement. The cement used was 50/50 poz. w/ 2% gell & 3% C.C. They recovered 1782' of 4 1/2" pipe. The plugging was accomplished by Allied Cementing. Mr. Bud Metz saw the top plug pumped.
Amount of Surface Casing: 8 5/8" @ 610' w/ 750 lbs cement.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luther
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 10-14-82

INV. NO. 1318-a