

*70*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1963

CONSERVATION DIVISION  
Wichita, Kansas

9-16-1963

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Leben Drilling Inc. 15-047-00281-0000

Complete Address: 905 Central Bldg., Wichita, Kansas

Lease Name Wallace Well No. # 1

Location C NW SW Sec. 12 Twp. 26 Rge. 16 (E) (W)W

County Edwards Total Depth 4470

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:00PM Day 14th Month Sept. Year 1963

The Above well was plugged as follows:

285' of 8 5/8" surface pipe, cemented with 275 sacks. 4000' of 4 1/2" long  
string, cemented with 125 sacks. Plugged back to 3100'. Top perferation  
3064'. Bottom hole was sanded to 3050', cemented with 3 sacks. Fluid level  
was up in hole. Plug was pushed to 275', 10' rock bridge, 6 sacks cement  
was mixed in barrel and put on plug through dump bailer, let set over  
night. Next morning hole failed to bail down. 15 sacks cement was mixed  
in barrel and put on plug through dump bailer, rock was added to plug.

let set over night. Next morning hole bailed down, and 10 sacks was added to  
plug. Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks  
I hereby certify that the above well was plugged as herein stated.  
to base cellar.

2200' of 4 1/2" long string was recovered  
from the hole

Signed: Archie Cliving  
Well Plugging Supervisor

INVOICED

DATE 9/16/63

INV NO 7936-4