

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

AUG 8 1966
8-8-1966
CONSERVATION DIVISION
WICHITA, KANSAS

15-047-00067-0000

Operator's Full Name Wichita Iron & Metals Corporation, Inc.

Complete Address: Box 13021, Wichita, Kansas

Lease Name Salsler Well No. # 1

Location SE SE Sec. 15 Twp. 26 Rge. 16 (E) (W)W

County Edwards Total Depth 4483'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:30AM Day 6th Month August Year 1966

The Above well was plugged as follows:

.408' of 8 5/8" surface pipe, cement circulated. 4480' of 5 1/2" long string,
cemented with 125 sacks. Top perforation 4436'. Bottom of the hole was sanded
to 4400', and cemented with 5 sacks. 2335' of 5 1/2" long string was recovered
from the hole. Bridge plug was pushed in fluid to 400', rock and sand bridge
from 400' to 390'. 5 sacks of cement was mixed in a barrel, and put on plug at
390', through the dump bailer, and let set over-night. Next day hole was bail-
ed dry, and 20 sacks of cement was added to the plug, Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-8-66
INV. NO. 3705-W