

15-151-20178-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
MAR 19 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Alpar Resources Inc

Complete Address Box 906 Perryton, TX

Lease Name L.L. Shaw Well No. 1

Location C NE/NW Sec. 20 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4478

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 4:00 PM Day 15 Month 3 Year 1973

The above well was plugged as follows:

334 ft 13' surface cemented with 400 sacks. 4477 ft 4 1/2 long string
cemented with 175 sacks. Top perf. 4040 ft. Push plug to 4000 ft,
3 sacks cement with bailer. Pulled 2200 ft 4 1/2. Pump 2 sacks hulls,
25 sacks gel, 150 sacks cement to surface.

Pumped by Allied Cementing Co Russell, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3-19-73
INV. NO. 7144-U