

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.
Complete Address Rt. 2 Great Bend, Ks
Lease Name Frazee Well No. 2
Location C SW/SW Sec. 17 Twp. 25 Rge. 14 (E) (W) W
County Stafford Total Depth 4260
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Santa Fe Pipe & Supply Inc.
Address Box 562 Great Bend, Ks License No. 574
Operation Completed: Hour 11:30 AM Day 22 Month 5 Year 1970

The above well was plugged as follows:

290 ft. of 8 5/8 surface pipe cemented with 225 sacks cement, 2% gel.,
2% G.C., & 50 sacks through 2" pipe. 4257 ft of 4 1/2 long string cem-
ented with 275 sacks posmix & 30 lbs. of 2% gel. Perf. at 3888-92ft.
& 3900-12 ft. Sand back to 3850 ft., 20 ft. sand & 4 sacks cement
with bailer. Pulled 2165 ft. of 4 1/2. Pumped 2 sacks hulls, 20 sacks
gel. & 100 sacks cement to surface. Globe Cementing Co. Great Bend. Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/25/70
INV. NO. 1942-W

Signed: M. Russell Bickerton
Well Plugging Supervisor