

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Bear "B" Well No. # 1

Location C SW NW Sec. 17 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4285

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11:30AM Day 22nd Month July Year 1963

The Above well was plugged as follows:

293' of 8 5/8" surface pipe, cement circulated with 225 sacks. 4282' of
5 1/2" long string, cemented with 125 sacks. Top perforation 4188'. Sanded
to 4170', cemented with 5 sacks. Hole was flowing with water, a squeeze
was necessary. Hole was squeezed with 10 sacks mud and 80 sacks cement,
with the plug on the bottom of the mud, through an 8 5/8" swage, with a
pressure of 150 lbs. This job was done by Globe Cementing Co.
3453' of 5 1/2" long string recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 7/24/63

INV. NO. 9464-W