

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 29 1965  
CONSERVATION DIVISION  
Wichita, Kansas  
3-29-65

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Kansas Exploration Company

Complete Address: 232 Bonnie Brae, Wichita, Kansas

Lease Name Bath Well No. # 1

Location NW SW SE Sec. 14 Twp. 25 Rge. 14 (E) (W)W

County Stafford Total Depth 4114'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling Inc.

Address: 912 Central Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 3:00PM Day 26th Month March Year 1965

The Above well was plugged as follows:

260' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid  
level in the hole was at 50'. 1st cementing plug and 1/2 sack of hulls  
was pushed in fluid to 240', and cemented with 25 sacks, through the  
drill pipe. Fluid level in the hole was now at 38', 2nd cementing plug  
bridged solid with dry cement and hulls on fluid at 38', and cemented  
with 10 sacks to the base of the cellar. Rat hole bridged and cemented  
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 3/29/65

INV. NO. 889-W