

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 3 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Thomas W. Clay

Complete Address: Suite 1010, Peoples National Bank Bldg., Tyler, Texas

Lease Name Tanner Well No. # 1

Location NE NE SE Sec. 14 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4330

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: This hole was washed down

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:00AM Day 2nd Month Feb. Year 1964

The Above well was plugged as follows:

327' of 8 5/8" surface pipe, cemented with 225 sacks. 4325' of 5 1/2" long string, cemented with 300 sacks. Plug back to 3900'. Top perforation 3871', plug was pushed to 3840', with 10' rock bridge, and cemented with 5 sacks. Fluid in hole would not bail down, plug was set at 275', with 15' rock bridge, and cemented with 2 sacks Cal-Seal, through dump bailer, and let set over night. Next morning hole would not bail down, due to a collapsed surface pipe. 25 sacks of cement was pumped into 240' of 2" tubing, on the bottom plug. Hole was mudded up to 30', bridged with rock and cemented with 8 sacks to base cellar. 2000' of 5 1/2" long string was recovered from the hole. I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 2/6/64

INV. NO. 8569-w