

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 7 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Smith Well No. # 1

Location NE SW NE Sec. 15 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4280

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 4:00PM Day 1st Month April Year 1964

The Above well was plugged as follows:

355' of 8 5/8" surface pipe, cement circulated. 3954' of 5 1/2" long string,
cemented with 150 sacks. Plug back to 3912'. Top perferation 3803. Bottom
of hole was sanded to 3790', and cemented with 5 sacks. Pipe was pulled
up to 450', and 10 sacks of Gel-Mud was pumped into pipe through 5 1/2"
swage. Pipe was pulled up to 360', and 25 sacks of cement was pumped into
5 1/2" pipe, through a swage. Pipe was pulled up to 180', and 10 sacks of
cement was pumped, through a swage. Plug was set at 40', with 10' rock
bridge, and cemented with 10 sacks to base cellar. 3033' of 5 1/2" long string
was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/9/64

INV. NO. 8909-W