



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Nadel & Gussman

Complete Address Box 14 Great Bend, KS

Lease Name Moody A Well No. 2

Location SE/SW/NE Sec. 7 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4262

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 10:00 AM Day 26 Month 9 Year 1974

The above well was plugged as follows:

318 ft 8 5/8 surface cemented with 200 sacks. 4262 ft 5 1/2 long string  
cemented with 100 sacks. Top perf. 4198 ft. Sand to 4170 ft, 5  
sacks cement with bailer. Pulled 2784 ft 5 1/2. Pump 3 sacks hulls,  
10 sacks gel, 100 sacks cement to surface.

Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 10/1/74

INV. NO. 9983-w