

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Nadel & Gusman

Complete Address Box 14 Great Bend, KS

Lease Name Bryant-Moore Well No. A-#1

Location SW/NW/NW Sec. 8 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4240

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 9:00 AM Day 27 Month 2 Year 1974

The above well was plugged as follows:

265 ft 8 5/8 surface cemented with 200 sacks. 4239 ft 5 1/2 long string
cemented with 125 sacks. Top perf. 4180 ft. Sand to 4100 ft, 5 sacks
cement with bailer. Pulled 2530 ft 5 1/2. Pump 2 sacks hulls, 10 sacks
gel, 100 sacks cement to surface.

Pumped by Allied Cementing Co Great Bend, KS

VOICED

I hereby certify that the above well was plugged as herein stated.

2/28/74

INV. NO. 8669-W

Signed: [Signature]
Well Plugging Supervisor