



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 16 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

15-047-00281-0000

Dear Sir:

Mr. Albert Schiffner of Forbes Casing Pulling Inc. has this date requested permission to plug the following described well:

Mr. Schiffner guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Inc.

Complete Address: 905 Central Bldg., Wichita, Kansas

Lease Name: Wallace Well No. # 1


Location: C NW SW Sec. 12 Twp. 26 Rge. 16 (E) (W) W

County Edwards Total Depth 4470 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Schiffner was instructed to plug the well as follows:

285' of 8 5/8" surface pipe, cemented with 275 sacks.  
4000' of 4 1/2" long string, cemented with 125 sacks. Plugged  
back to 3100'. Top perforation 3064'. Sand to 3050', cement  
with 3 sacks. Fill hole with mud to 275, 10' rock bridge,  
cement with 20 sacks. Fill hole with mud to 40', 10' rock  
bridge, cement with 10 sacks to base cellar.

Very truly yours,  
  
 Conservation Division Agent