



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-151-30027-0000

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1965

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas
8-16-65

Dear Sir:

Mr. Paul Gatlin of Anadarko Production Co. has this date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Reiman "C" Well No. # 1

Location: 1980' FWL & 4620' FSL Sec. 2 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4200' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

359' of 8 5/8" surface pipe, cement circulated with 450 sacks.
Fill hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving