

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 2 1964

J. P. Roberts.  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Joe Cain Jr. of Navajo Drilling Co. has this  
 date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co. & Navajo Drilling Co.

Complete Address: 6810 W. Highway 54, Wichita, Kansas

Lease Name: Webster Well No. # 1

Location: SW NW NE Sec. 14 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4230 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cain was instructed to plug the well as follows:

204' of 8 5/8" surface pipe, cement circulated. Fill hole  
with drilling mud. Spot 20 sacks cement at 325', through  
drill pipe. Spot 20 sacks cement at 180', through drill  
pipe. Fill hole with mud to 40', plug, bridged with hulls,  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent