

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dough Boyd of Leben Drilling Inc. has this
date requested permission to plug the following described well:

Mr. Boyd guarantees payment of the plugging fee.

Operator's full Name: Kansas Exploration Company

Complete Address: 232 Bonnie Brae, Wichita, Kansas

Lease Name: Bath Well No. # 1

Location: NW SW SE Sec. 14 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4114 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Boyd was instructed to plug the well as follows:

260' of 8 5/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 240', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
10 sacks to base cellar. Bridge and cement rat hole with 2
sacks.

Very truly yours,

Achie Elving
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1965
CONSERVATION DIVISION
Wichita, Kansas
3-29-65