


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Pratt County. Sec. 11 Twp. 26S Rge. (E) 15 (W) 15
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE
Lease Owner Anderson Prichard Oil Corporation
Lease Name Long Well No. 1
Office Address Box 142, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) DRY
Date well completed Aug. 28, 1952
Application for plugging filed Sept. 11, 1952
Application for plugging approved Sept. 12, 1952
Plugging commenced Sept. 13, 1952
Plugging completed Sept. 20, 1952
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 223 3964 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	370'	8-5/8"	383.17' 0A	none
				5-1/2"	4150'	2564'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3964' to 3960' Crushed Rock, 5 sx cmt.
Shot casing off at 2564'
Pulled casing
Heavy mud to 300'
Set rock bridge, dumped 20 sx cmt.
Heavy mud to 30' from surface
10 sx cmt. for cap on well

RECEIVED
CORPORATION COMMISSION
SEP 29 1952
9-29-1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to W. J. Dearen
Address Box 142, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Gerald M. Dougherty (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty
Box 142, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of September, 19 52

Verdella M. Hartman
Notary Public.

My commission expires December 4, 1954

PLUGGING
FILE SEC 11 T 26 R 15
BOOK PAGE 44 LINE 23

15.151-00344-0000

DRILLER'S
LOG

Company: Anderson-Prichard Oil Corporation
Contractor: Peel Brothers, Inc.

SW SW NE
Sec. 11, Twp. 26S, Rge. 15W

Farm: W. I. Long Well No. 1
Comm: 8-4-52 Comp: 8-28-52

County: Pratt,
Kansas

Total Depth: 4572'

Elevation:

Casing: 8 5/8" @ 370'
5 1/2" @ 4150'

Production:

Figures below indicate bottom of formations

Sand	0'	250
Shale		300
Redbed		835
Redbed and Shale		945
Anhydrite		970
Shale and Shells		1800
Broken Lime		1890
Broken Lime and Shale		2020
Lime and Shale		2140
Broken Lime		2215
Lime and Shale		2380
Lime		2485
Lime and Shale		3625
Lime		4275
Lime and Shale		4313
Lime and Chert		4335
Lime		4360
Lime and Chert		4488
Lime		4512
Dolomite		4572
Total Depth		4572

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.,

BY: Mendell L. Peel

SUBSCRIBED AND SWORN to before me this 28th day of August, 1952.

RECEIVED
NOTARY COMMISSION
12 1952
Bernice L. Irwin
Notary Public-Barton County, Kansas

My commission expires: April 23, 1955.

11-26-15W
44-22