


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Pratt County. Sec. 20 Twp. 26S Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines C NW/4 SE/4
Lease Owner Stickle Drilling & Drilling & Exploration
Lease Name Curtis Well No. 1
Office Address 1027 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 8 1959
Application for plugging filed April 7 1959
Application for plugging approved April 7 1959
Plugging commenced April 8 1959
Plugging completed April 8 1959
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Merle Rives
Producing formation None Depth to top - Bottom - Total Depth of Well 4690 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Unknown	Water	Surface	150'	8-5/8"	1006'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mixed mud in pits thoroughly with jets and placed heavy rotary mud from total depth to 300 feet through drill pipe.

A Halliburton plug and 1/3 sack of hulls were placed at 300 feet with with 20 sacks of cement placed on top through the drill pipe.

Heavy rotary mud was then ^{placed} to 35 feet.

A Halliburton plug and 1/3 sack of hulls were placed at 35 feet with 10 sacks of cement placed on top of this through the drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stickle Drilling Company
Address 1027 Union Center

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clifford M. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clifford M. Smith
1027 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April 19 59.

My commission expires 17 February 1962

Charley V. Shank
Charley V. Shank, Notary Public.

PLUGGING
FILE SEC 20 T. 26 R. 15W
BOOK 30 LINE 24

15-151-00314-0000

Stickle Drilling Company, Production
Wichita, Kansas

Tulsa, Oklahoma
April 13, 1959

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: March 21, 1959
Drilling Completed: April 8, 1959

No. 1 Curtis #165 C NW
SE 20-26S-15W, Pratt
County, Kansas.

DRILLERS LOG

Total Depth Figures Indicate Base of Formation:

Surface	0
Shale & Sand	342
Red Bed	640
Red Bed & Sand	970
Red Bed & Shale	975
Red Bed	1000
Anhydrite	1025
Shale & Shells	1960
Lime & Shale	2255
Lime & Shale Streaks	2415
Lime & Shale	2475
Shale & Lime	2520
Lime & Shale	2645
Shale & Lime	3125
Lime	3185
Lime & Shale	3815
Shale	3892
Lime	4240
Lime & Shale	4310
Lime	4383
Lime & Chert	4436
Cherty Lime	4493
Lime & Chert	4521
Cherty Lime	4574
Lime Chert	4609
Shale & Sand	4660
Lime & Shale	4690 TD

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1959
CONSERVATION DIVISION
WICHITA, KANSAS

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Stickle Drilling Company's, (Production) No. 1 Curtis (#165) C NW SE 20-26S-15W, Pratt County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

PLUGGING
FILE SEC. 20 T. 26 R. 15W
BOOK PAGE 30 LINE 24