


15-151-20178-0000

Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Pratt County, Sec. 20 Twp. 26S Rge. 15W (E) (W)  
Location as "NE/CNWSW" or footage from lines C NE NW  
Lease Owner Alpar Resources, Inc.  
Lease Name ~~XXXXXX~~ L. L. Shaw Well No. 1  
Office Address Perryton, Texas 79070  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 8-24-71 19  
Application for plugging filed 19  
Application for plugging approved 2-26-73 19  
Plugging commenced 3/9/73 19  
Plugging completed 3/15/73 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 1-4-73 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Lansing Kansas City Depth to top 4040 Bottom 4047 Total Depth of Well 4478 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing Kansas City	oil	4040	4047	13"	334	none
				4 1/8"	4477'	2302'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4370', pushed plug to 4000' and ran 3 sacks of cement. Loaded hole, shot pipe at 3381', 2620', 2603', 2449', 2292', pulled 70 joints. Pumped 2 sacks hulls, 25 sacks gel and 150 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 23 1973

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet) KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*  
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 19th day of March, 19 73

My commission expires \_\_\_\_\_  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

*Margaret Melcher*  
Notary Public.

# WELL LOG


15-151-20178-0000

COMPANY **Alpar Resources, Inc.**  
 FARM **L. L. Shaw** NO. **1**  
 TOTAL DEPTH **4478'**  
 COMM. **7-15-71** COMP. **7-25-71**  
 CONTRACTOR **Garvey Drilling Company**

SEC. **20** T. **26B** R. **19W**  
 LOC. **NE NW**  
 COUNTY **Pott, Kansas**

CASING

**1 3/4" @ 934' w/400sx**  
**4 1/2" @ 4477' w/175sx**



ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 193' Sand
- 950' Red Bed & Shale
- 1028' Anhydrite
- 1390' Shale
- 1450' Shale & Lime
- 1812' Shale
- 2145' Lime & Shale
- 2305' Lime
- 2640' Lime & Shale
- 2810' Shale & Lime
- 3280' Lime & Shale
- 3570' Lime
- 3615' Lime & Shale
- 3720' Lime
- 4360' Lime & Chert
- 4375' Shale
- 4442' Viola
- 4478' Viola
- 4478' STD

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 26 1973  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of **Kansas** }  
 County of **Barton** } SS

I, **Charlene Marker** of **Garvey Drilling Company**  
 upon oath state the above and foregoing is a true and correct copy of the log of the **L L Shaw No. 1** well.

Subscribed and sworn to before me this **2nd** day of **August** 19 **71**

My Commission Expires: **July 3, 1974**

*Charlene Marker*  
*James A. [Signature]*  
 NOTARY PUBLIC