


15-151-66117-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 21 Twp. 26S Rge. 15 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE
Lease Owner Tatlock Oil Company
Lease Name E. W. Curtis Well No. 1
Office Address 321 West Douglas, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 11, 19 53
Application for plugging filed April 15, 19 53
Application for plugging approved April 16, 19 53
Plugging commenced April 20, 19 53
Plugging completed May 5, 19 53
Reason for abandonment of well or producing formation Non-productive in
Kansas City and Mississippi
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation Mississippi Depth to top Bottom Total Depth of Well 4638 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite				8-5/8"	842'	None
Mississippi				5-1/2"	4457'	3000' (Approx.)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Solid rock bridge at 3700'. Dumped 5 sacks cement.
Mudded hole to 300' installed solid rock bridge
and dumped 20 sacks cement. Mudded hole to 35' and
capped with 10 sacks cement to cellar base.

RECEIVED
MAY 7 1953
CONSERVATION DIVISION
Wichita, Kansas

3-7-1953

Plugging Contractor: Morgan Well Plugging Service
102 West 18th Street
Hutchinson, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Tatlock Oil Company
Address same as above

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Tom Tatlock, employee of owner (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) TATLOCK OIL COMPANY
by: Tom Tatlock, Partner
Same as above (Address)

SUBSCRIBED AND SWORN to before me this 6th day of May, 19 53

Lois Denton

Notary Public.

My commission expires January 28, 1956

PLUGGING
FILE SEC 21 T 26 R 15 W
BOOK PAGE 93 LINE 35

15-151-00117-0000

Curtis Well No. 1

SE-SE-NE
Section 21-26s-15w
Pratt County, Kansas

Contractor: The R. W. Rine Drilling Company
Started: 3-7-53 Finished: 3-26-53

	LOG	
Sand	0	40
Sand Clay Shale	40	350
Red Bed	350	500
Red Bed	500	835
Anhydrite	835	854
Lime & Sand	854	1485
Shale	1485	1740
Shale & Lime	1740	1995
Lime	1995	2475
Lime	2475	2620
Shale & Lime	2620	3005
Lime & Shale	3005	3150
Lime & Shale	3150	3385
Lime	3385	3700
Lime & Shale	3700	3795
Lime	3795	3845
Shale & Lime	3845	3950
Lime	3950	4000
Lime	4000	4125
Lime	4125	4220
Lime & Shale	4220	4285
Lime & Shale	4285	4325
Lime	4325	4390
Lime & Chert	4390	4415
Chert & Lime	4415	4433
Lime, Chert & Shale	4433	4455
Lime & Shale	4455	4505
Lime & Shale	4505	4529
Lime, Shale & Chert	4529	4555
Lime & Shale	4555	4600
Lime, Shale, Chert	4600	4630
Lime	4630	4665
Lime, Shale	4665	4697
Lime & Shale	4697	4638

Syfo @ 500' $\frac{1}{2}^{\circ}$
8-5/8" csg. @ 842' w/340 sx 4% gel
63 sx stratcrete 100#
Syfo 1000' $\frac{3}{4}^{\circ}$
Syfo @ 1660' $\frac{3}{4}^{\circ}$
Syfo @ 1925' 1°
Syfo @ 2180' $\frac{1}{2}^{\circ}$ Syfo @ 2410' $\frac{1}{2}^{\circ}$
Syfo @ 2575' $\frac{1}{4}^{\circ}$

Syfo @ 3050' $\frac{1}{4}^{\circ}$

Syfo @ 3750' $\frac{1}{4}^{\circ}$

Syfo @ 4220' 0°

5 1/2" csg. @ 4457' w/200 sx

I, R. M. Green, do hereby certify that the above is a true and accurate log of the Curtis Well No. 1, located SE-SE-NE, Section 21-26s-15w, Pratt County, Kansas

/s/ R. M. Green
Assistant Secretary

Subscribed to and sworn before me this 6th day of April, 1953

-seal-

/s/ Leona V. Pederson
Notary Public

My Commission expires April 20, 1955.

COMPLETION DATA

Perforated Kansas City Lime from 3944 to 3956. Zone acidized and produced water.
Zone squeezed with 191 sacks of cement for a complete shut off.

Perforated Mississippi Limestone from 4406 to 4417. Acid frac with 1900 pounds sand. Producing 3/4 barrel fluid per hour - trace of oil.

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1953
CONSERVATION DIVISION
Wichita, Kansas
PLUGGING
FILE SEC 21 T 26 S 15W
BOOK PAGE 93 LINE 35