

15-185-60008-0000

WELL PLUGGING RECORD.

Give All Information Completely  
 Make Required Affidavit

COUNTY Stafford SEC. 17 TWP. 25 RGE. 14 E/W  
 Location as in quarters or footage from lines:  
C/NW/SW


Lease Owner Petroleum, Inc.  
 Lease Name Frazee Well No. #1  
 Office Address Box 1447 - Great Bend, Ks. 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced August 16, 1983  
 Plugging completed August 23, 1983  
 Reason for abandonment of well or producing formation  
Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4453'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	253'	NONE
				5 1/2"	4330'	294.67'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped sand to 3675' and five (5) sacks cement.  
 Pulled nine (9) joints 5 1/2" casing.  
 Squeezed well with two hundred fifty (250) sacks  
 60/40 pozmix cement with 2% added gel and 3% calcium  
 chloride. No shutin pressure.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.  
 (Address) - 67530

SUBSCRIBED AND SWORN TO before me this 1st day of September 1983



Margaret Prosser  
 Notary Public.  
 STATE CORPORATION COMMISSION  
 RECEIVED  
 SEP 2 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas  
9-2-1983

My Commission expires \_\_\_\_\_

# WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 17 T. 25S R. 14W

FARM FRAZEE NO. 1


LOC. Approx. C-NW, SW

TOTAL DEPTH 4455'

COUNTY STAFFORD CO., KANSAS

COMM. March 25, 1961 COMP. April 7, 1961

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 253' w/250 sax.  
5 1/2" @ 4330.25' w/250 sax.

ELEVATION 1983' GL

PRODUCTION K.C. & Viola

FIGURES INDICATE BOTTOM OF FORMATIONS

RECEIVED  
STATE CORPORATION COMM.  
AUG 12 1963

200	Surface soil & sand
254	Shale
925	Shale & shells
938	Anhydrite
1505	Shale & shells
1925	Red bed & shale
2125	Shale, shells & lime
2290	Lime
2465	Shale
2860	Lime & shale
3035	Shale & lime
3588	Lime & shale
4079	Lime
4161	Lime & shale
4175	Lime
4260	Lime & shale
4312	Cherty lime
4366	Lime & chert
4395	Shale & sand
4455	Shale & lime
4455	T. D.

State of KANSAS  
County of BARTON } SS

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 FRAZEE well.

Verne A. Morris

Subscribed and sworn to before me this 14th day of April 19 61

My Commission Expires: April 14, 1963

Arthur J. Niles  
NOTARY PUBLIC