


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 17 Twp. 25S Rge. 14W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NE  
Lease Owner Alpine Oil & Royalty Co., Inc.  
Lease Name Hall Well No. 1  
Office Address 1100 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 24, 1956 19  
Application for plugging filed November 24, 1956 19  
Application for plugging approved November 24, 1956 19  
Plugging commenced November 24, 1956 19  
Plugging completed November 24, 1956 19  
Reason for abandonment of well or producing formation non-productive

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4470 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	254'	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud from 4470 feet, total depth, to 248 feet;  
1/3rd sack hulls, plug and 20 sacks cement mud to  
41 feet; 1/3rd sack hulls and another plug and 10  
sacks cement to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.  
Address 1100 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
1100 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 19 56

My commission expires August 10, 1957

Virginia Mordell  
Notary Public.  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 17 T. 25 R. 14W  
BOOK PAGE 119 LINE 16

NOV 27 1956  
CONSERVATION DIVISION  
Wichita, Kansas  
11-29-1956

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: November 8, 1956

Contractor: Quaker Drilling Co., Inc.

Completed: November 24, 1956

Hall No. 1  
SW SW NE Section 17-25S-14W  
Stafford County, Kansas

Elevation: 1988 K. B.

Production: D & A

Casing Record:

Set 254 feet of 8 5/8 inch casing with 225 sacks pozmix

(Figures Indicate the Bottom of Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	185	Anhydrite	895
Shale & Shells	254	Heebner	3575 -1587
Red Bed & Shale	425	Brown Lime	3715 -1727
Sand & Shale	490	Lansing	3745 -1757
Red Bed & Shale	895	Conglomerate	4139 -2151
Anhydrite	915	Mississippi	4169 -2181
Shale & Shells	1275	Kinderhook	4178 -2190
Shale	1565	Viola	4238 -2250
Shale & Lime	1965	Arbuckle	4423 -2435
Lime	2185	Rotary Total Depth	4470 -2482
Lime & Shale	3815		
Lime	3865		
Lime & Shale	4170		
Lime	4180		
Shale	4200		
Shale & Lime	4315		
Cherty Lime & Shale	4365		
Sandy Lime & Shale	4415		
Lime & Shale	4470		

I hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW SW NE of Section 17, Township 25 South, Range 14 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. M. Case  
President

SUBSCRIBED AND SWORN to before me a Notary Public this 26th day of November, 1956.

Virginia M. M. Case  
Notary Public

MY COMMISSION EXPIRES:  
August 10, 1957

PLUGGING  
FILE SEC 12 T 25 R 14 W  
BOOK PAGE 119 LI E 16

RECEIVED  
STATE CORPORATION COMMISSION

NOV 27 1956

CONSERVATION DIVISION  
Wichita, Kansas