


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 14 Twp. 25S Rge. 14 (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines C NW NW NW  
Lease Owner Musgrove Petroleum Corporation  
Lease Name TANNER Well No. 1  
Office Address 801 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed October 14, 1958 19 58  
Application for plugging filed verbally October 13, 1958 19 58  
Application for plugging approved verbally October 13, 1958 19 58  
Plugging commenced October 14, 1958 19 58  
Plugging completed October 14, 1958 19 58  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4310 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	332'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 240'.  
1st plug set at 240' w/ 1/2 sk hulls & 20 sx cement.  
Filled hole with heavy mud to 35'.  
2nd plug set at 35' w/ 1/2 sk hulls & 10 sx cement.


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 801 Union Center, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Emil E. Bowers (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers801 Union Center, Wichita, Kansas.  
(Address)SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 58My commission expires June 16, 1959.

Leah Faye Heike Notary Public.  
RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1958  
10-22-1958

# CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	TANNER #1
LOCATION:	C NW NW NW, Sec. 14-25S-14W Stafford County, Kansas
COMMENCED:	September 30, 1958
COMPLETED:	October 14, 1958

0	40	Surface soil
40	160	Sand
160	335	Shale & shells
335	740	Shale
740	1540	Shale & red bed
1540	1595	Shale & shells
1595	1915	Shale & red bed
1915	3080	Shale & lime
3080	3240	Sandy lime & shale
3240	3605	Lime & shale
3605	3698	Lime
3698	3793	Lime & shale
3793	3835	Lime
3835	3885	Lime & shale
3885	3925	Lime & chert
3925	4015	Lime
4015	4032	Lime & shale
4032	4060	Conglomerate & chert
4060	4103	Lime & chert
4103	4155	Shale & chert
4155	4162	Lime
4162	4181	Lime & shale
4181	4265	Lime
4265	4296	Lime & shale
4296	4310	Lime
	4310	Rotary Total Depth

ELEVATION:	1974'	K. B.	Mississippi	4079'	(-2105)
TOPS: (Schlumberger)			Viola	4180'	(-2206)
Heebner	3508'	(-1534)	Simpson	4247'	(-2273)
Brown Lime	3654'	(-1680)	Arbuckle	4285'	(-2311)
Lansing	3679'	(-1705)	T. D.	4307'	
Base K. C.	3976'	(-2002)			

Set 8-5/8" surface casing at 332' with 275 sacks cement.

Dry and Abandoned.

STATE OF KANSAS	}	SS
COUNTY OF SEDGWICK		

I, EMIL E. BOWERS, do hereby certify that the above and foregoing is a true and correct copy of the log of the TANNER #1, C NW NW NW, Section 14-25S-14W, Stafford County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

PLUGGING	
FILE	SEC 14 T 25 R 14W BY
BOOK	PAGE 130 LINE 7

Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 21st day of October, 1958.

OCT 22 1958

CONFIRMATION DIVISION

*Leah Faye Heike*  
Leah Faye Heike, Notary Public

My commission expires June 16, 1959.