


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 15 Twp. 24 Rge. 25 (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines NE SW NE  
Lease Owner Santa Fe Pipe & Supply Company  
Lease Name Smith Well No. 1  
Office Address Box 562, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed MARCH 23 1964  
Application for plugging approved MARCH 25 1964  
Plugging commenced March 24 1964  
Plugging completed April 1 1964  
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4280 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	355	8 5/8"	355	none
		0	3954	5 1/2"	3954	3025.03

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Push plug to 3790', set 10' rock bridge and dump 5 sacks of cement.

Pump in 10 sacks of mud at 450'. Pump in 20 sacks of cement at 350'.

Pump in 10 sacks of cement at 180'. Cap with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 2 1964

CONSERVATION DIVISION  
Wichita, Kansas

6-2-1964

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Dean Wells (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells

Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of April, 1964

J. Rader  
Notary Public.

My commission expires July 7, 1964

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPIES

Company: MUSGROVE PETROLEUM CORP.  
Farm: Smith No. 1

SEC. 15 T. 25 R. 14W  
NE SW NE

Total Depth. 4280'  
Comm. 4-10-59 Comp. 4-27-59  
Shot or Treated.  
Contractor.  
Issued. 6-25-60

County. Stafford  
KANSAS



Elevation. 1970 RB

Production. 149 BOPD

CASING:

8 5/8" 355' cem. w/175 sx.  
5 1/2" 3954' cem. w/150 sx.

Figures Indicate Bottom of Formations.

surface sand	150
clay & shells	305
red bed	355
shale, shells & red bed	810
red bd	880
anhydrite	920
shale & shells	1760
lime & shale	3155
lime	3278
lime & shale	3373
lime	3522
lime & shale	3642
lime	3812
lime & shale	3841
lime	4107
lime & shale	4138
lime	4204
lime & shale	4263
lime	4280 RTD
Total Depth	

TOPS: SCHLUMBERGER

Heebner	3492
Brown Lime	3640
Lansing	3670
Base Kansas City	3961
Mississippi	4064
Viola	4140
Simpson	4220
Arbuckle	4256

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN-2 1964

CONSERVATION DIVISION  
Wichita, Kansas