


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 6 Twp. 25 Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines SW NE NE
Lease Owner Westgate-Greenland Oil Company
Lease Name Roy Wilson Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 20, 1952 19
Application for plugging filed December 20, 1952 (orally) 19
Application for plugging approved December 20, 1952 19
Plugging commenced December 20, 1952 19
Plugging completed December 20, 1952 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface		0	222	8 5/8"	222	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set:

Filled hole with heavy mud from total depth to 220 feet
Set plug at 220 feet and ran 20 sacks cement to 160 feet
Filled with heavy mud from 160 to 35 feet
Set plug at 35 feet and ran 10 sacks cement to cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Westgate Drilling Corporation
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Don Allen (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Allen
1009 Central Building, Wichita, Kans
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 52

My commission expires May 25, 1953.

Esther Russell
Notary Public.

PLUGGING
FILE SEC 6 T 25 R 142
BOOK PAGE 68 LINE 1

RECEIVED
STATE CORPORATION COMMISSION

DEC 24 1952
CONSERVATION DIVISION
Wichita, Kansas
12-24-1952

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: Westgate Drilling Corporation
 FARM: Roy Wilson No. 1
 LOCATION: SW NE NE Section 6-25S-14W
 Stafford County, Kansas
 COMMENCED: December 5, 1952
 COMPLETED: December 20, 1952
 ELEVATION: 2003 DF

0	to	90	Sand
90	to	160	Shale and sand
160	to	222	Shale and shells
222	to	942	Red bed and shale
942	to	979	Anhydrite
979	to	1700	Shale and shells
1700	to	1850	Shale and lime
1850	to	2090	Lime
2090	to	3588	Shale and lime
3588	to	3750	Lime
3750	to	3807	Shale and lime
3807	to	4062L	Lime
4062	to	4163	Shale and lime
4163	to	4210	Shale
4210	to	4308	Lime and chert
4308	to	4410	Shale
4410	to	4440	Arbuckle
		4440	T. D. (RB)

Set 222 feet of 8 5/8" surface. Cemented with 225 sacks cement and 3 sacks calcium chloride.

TOPS: Anhydrite	940	Lansing	3752	Kinderhook	4151
Heepner	3581	Base KC	4031	Viola	4207
Brown Ls	3719	Cherty Cong	4129	Simpson	4347
		Miss. Chert	4141	Arbuckle	4396

Drill Stem Test 3881-3938, open 1 hour, rec. 85' mud,
 BHP 1250#.

Run Schlumberger

Dry, plugged and abandoned

C E R T I F I C A T E

I, Don Allen, do hereby certify that the above and foregoing is a true and correct copy of the log of the Roy Wilson #1, SW NE NE Section 6-25S-14W, Stafford County, Kansas, as reflected by files of the Westgate-Greenland Oil Company.

Don Allen
 Don Allen

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this ~~18th~~ 23rd day of December, 1952.

Esther Unsell
 Esther Unsell, Notary Public

My commission expires May 25, 1953.

PLUGGING
 FILE SEC 6 T 25 R 14W
 BOOK 68 LINE 1

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 24 1952
 CONSERVATION DIVISION
 Wichita, Kansas