


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 6 Twp. 25S Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Chief Drilling Co., Inc.
Lease Name WILSON Well No. 1
Office Address P.O. Box 797, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-24- 19 62
Application for plugging filed 1-24- 19 62
Application for plugging approved 1-24-6 19 62
Plugging commenced 1-24- 19 62
Plugging completed 1-24- 19 62
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lamkamp, Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sand & Gravel		-0-	294'	8-5/8"	294'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/3 sack hulls, set wooden plug @ 240' with 20 sacks cement thru drill pipe
1/3 sack hulls, set wooden plug @ 35' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1962

CONSERVATION DIVISION
Wichita, Kansas

1-30-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address P.O. Box 797, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P.O. Box 797, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 1962

My commission expires June 18, 1963

Dorothy B. John
Dorothy B. John

Notary Public.

JAN 30 1962

CONSERVATION DIVISION
Wichita Kansas

WELL LOG

Chief Drilling Co., Inc.
P.O. Box 797
Great Bend, Kansas

WILSON #1
C SW 1/4 Sec. 6-25N-14W
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: January 11, 1962
Completed: January 24, 1962

Casing Record: 8-5/8" surface pipe at 294' with 250 ex Sunset Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand	0	120	2005' Gr.
Shale	120	425	2007' D.F.
Redbed & Shale (and streaks)	425	946	2010' K.B.
Anhydrite	946	975	
Shale & Shells	975	1998	
Shale & Lime	1998	2125	<u>FORMATION TOPS</u>
Lime	2125	2345	
Shale & Lime	2345	3335	
Lime	3335	3540	
Lime & Shale	3540	3642	
Shale	3642	3767	
Lime	3767	4034	
Lime & Shale	4034	4184	
Chert	4184	4246	
Shale	4246	4307	
Chert & Lime	4307	4355	
Total Depth	4355		

	<u>Sample</u>	<u>Log</u>
Anhydrite(drillers)	946	
Heebner	3603	3603
Toronto	3625	3627
Douglas	3642	3644
Brown Lime	3752	3753
Lansing	3767	3768
Base K.C.	4034	4034
Conglomerate	4184	4188
Mississippi	4208	4210
Kinderhook	4246	4249
Viola	4307	4309
Total Depth	4355	4357

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW 1/4 Sec. 6-25N-14W, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

W. Richard Hoover
W. Richard Hoover, President

Subscribed and sworn to before me this 25th day of January, 1962

Dorothy B. John
Dorothy B. John, Notary Public

My commission expires: June 18, 1963