

9-15-87

To: 1 060998
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,706-0000

W/2 SE SE, SEC. 17, T 26 S, R 15 W/EX

660 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Doggett Well # 2

Operator: Mull Drilling Company, Inc.

County Pratt 144.72

Name & Address P.O. Box 2758

Well Total Depth 4453 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 443

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Box 963, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 15 Month: 9 Year: 19 87

Plugging proposal received from Gene Brown

(company name) Mull Drilling Company, Inc. (phone) 316-254-7382

were: 5 1/2" at 4449' PBD 4400' Perfs at 4045-56'

1st plug pump 25 sx cement with 3 sx hulls at 4050' down 5 1/2",

2nd plug pump 50 sx cement at 1000-0',

3rd plug pump 35' sx cement down annulus - 8 5/8" X 5 1/2".

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 15 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 25 sx cement down 5 1/2",

2nd plug pumped water spacer to fill to 1000' and pumped 50 sx cement. Filled 5 1/2" to 0'.

3rd plug pumped 35 sx cement down 8 5/8" annulus.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 100 psi and shut in 50 psi - 5 1/2".

SEPT 17 1987

Maximum pressure 200 psi and shut in 100 psi - 8 5/8".

9-17-87

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used Econolite cement by Halliburton. No recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
I () do hereby acknowledge and agree to observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 9-23-87

INV. NO. 18179