

9-15-87

To: 1 060999
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- 151-20,754-0000

SW NW NW, SEC. 17, T 26 S, R 15 W/E
4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Doggett Well # 4

Operator: Mull Drilling Company, Inc.

County Pratt 144.63

Name & Address P.O. Box 2758

Well Total Depth 4450 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Box 963, Pratt, KS 67124

Company to plug at: Hour: 3 p.m. Day: 15 Month: 9 Year: 19 87

Plugging proposal received from Gene Brown

(company name) Mull Drilling Company, Inc. (phone) 316-254-7382

were: 4 1/2" at 4457' Perfs at 4350-58, 4038-42'

1st plug pump 25 sx cement with 3 sx hulls at 4042' down 4 1/2",

2nd plug pump 35 sx cement at 1000-0',

3rd plug pump 45 sx cement down annulus-8 5/8" X 4 1/2".

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 15 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls with 25 sx cement down 4 1/2",

2nd plug filled 4 1/2" to 1000' with water and pumped 50 sx cement to fill 4 1/2" to 0',

3rd plug pumped 45 sx cement down 8 5/8" annulus.

Plugged water well from TD to 5'.

Maximum pressure 1200 psi and shut in 600 psi.- 4 1/2".

Maximum pressure 350 psi and shut in 150 psi - 8 5/8".

Remarks: Used Econolite by Halliburton. No recovery.

(If additional description is necessary, use BACK of this form.)

I (the undersigned) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED
DATE 9-23-87
INV. NO. 18177

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1987
9-17-87
CONSERVATION DIVISION
Wichita, Kansas