

1 080520

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 150'W SW SE, SEC. 17, T 26 S, R 15 W/EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,919-0000  
660 feet from S section line  
2130 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5144  
Operator: Mull Drilling Company, Inc.  
Name & Address: P. O. Box 2758  
Wichita, KS 67201

Lease Name Doggett Well # 5  
County Pratt 145.02  
Well Total Depth 4462 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 442

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mull Drilling Company License Number 5144  
Address P. O. Box 2758, Wichita, KS 67201

Company to plug at: Hour: 3:15 pm Day: 1 Month: May Year: 19 86

Plugging proposal received from Jerry Brown  
(company name) Mull (phone) 316-264-6366

were: 4 1/2" at 4461' PBD 4420' Perfs at 4366-4368'  
1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00 pm Day: 1 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

Maximum pressure 200 psi and shut in 125 psi

Remarks: Recovered 2000' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
MAY 12 1986  
Observe this plugging.

Signed *J. P. [Signature]*  
(TECHNICIAN)

DATE \_\_\_\_\_  
INV. NO. 13789

STATE CORPORATION COMMISSION  
MAY 12 1986  
CONSERVATION DIVISION  
Wichita, Kansas