

1 061000  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-15-87  
API NUMBER 15- 151-20,920 -0060  
100' E of  
NW NW NE, SEC. 17, T 26 S, R 15 (W/E)  
4950 feet from S section line  
2210 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144  
Operator: Mull Drilling Company, Inc.  
Name &  
Address P.O. Box 2758  
Wichita, KS 67201

Lease Name Doggett Well # 6  
County Pratt 144.63  
Well Total Depth 4450 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 444

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:15 a.m. Day: 15 Month: 9 Year: 19 87

Plugging proposal received from Gene Brown

(company name) Mull Drilling Company, Inc. (phone) 316-254-7382

were: 4 1/2" at 4449' Perfs at 4342-4350'

1st plug pump 25 sx cement with 3 sx hulls at 4350' down 2 3/8" tubing,

2nd plug pump 35 sx cement at 1000-0',

3rd plug pump 45 sx cement down annulus - 8 5/8" X 4 1/2".

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 15 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls mixed with 25 sx cement,

2nd plug pulled tubing to 1054' and filled hole to 1054' with water and spotted 35 sx cement filling 4 1/2" to 0',

3rd plug pumped 45 sx cement down 8 5/8" annulus.

Maximum pressure 200 psi and shut in 50 psi 8 5/8".

Remarks: Used Econolite by Halliburton. No recovery.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Paul A. Luthie (TECHNICIAN)

DATE 9-23-87

INV. NO. 18180