

To: 1 040643 4-7
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- D-19,991 (5-15)-2062709 R
75' SW of
C NE NE, SEC. 20, T. 26 S, R. 15 W/EX
4567 feet from S section line
713 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30349
Operator: Vess-Transpacific Operating Co.
Name & Address: P.O. Box 781350
Wichita, KS 67228

Lease Name Shaw Well # A-1
County Pratt 120.54
Well Total Depth 3709 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 430

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well D&A _____
Other well as hereinafter indicated _____ Dual Completion

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 7 Month: 4 Year: 19 92

Plugging proposal received from Manny Boatwright
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 7" at 3685' w/23Q sx cement, Perfs at 2309-28' gas zone, 3432-38 & 3626-34' -SWDW zones
1st plug sand back to 2278' and dump 7 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 60 sx cement, 10 sx gel, 100 lbs. hulls, release
10 3/4" wiper plug and pump 190 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 7 Month: 4 Year: 19 92.

ACTUAL PLUGGING REPORT 1st plug sanded back to 2278' and dumped 7 sx cement on top of
sand bridge through bailer,
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 60 sx cement,
10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 190 sx cement.
Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 7" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (operator) observe this plugging.

DATE 4-28-92
INV. NO. 35098

Signed *Stephan R. Pifer*
(TECHNICIAN)